

69

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 25 1961
 9-25-67
 CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Clinton Oil Co. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: 6810 West Highway 54, Wichita, Kansas

Lease Name: DeMoss B Well No. 3

Location: C N/2 SW ~~SW~~NW AUB Sec. 12 Twp. 26 Rge. 2 (E) (W) /

County Sedgwick Total Depth 2872' Oil Well X

Gas Well Input Well SWD Well D & A III Lost Hole

Mr. Pulley was instructed to plug the well as follows:

- 8 5/8"-167'-Circulated w/cement. 5 1/2"-2849'-Cemented. Sand hole to 2800'.
- 5 Sax.cement 2800' to 2750'. Mud 2750' to 180'. Bridge 180' to 170'.
- 25 Sax.cement 170' to 100'. Mud 100' to 40'. Bridge 40' to 30'.
- 10 Sax.cement 30' to 0. Pulled 2420'-5 1/2"-pipe.

Very truly yours,

Hugh Scott
 Conservation Division Agent