

9

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1967
9-21-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Clinton Oil Co. has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Co.

Complete Address: 6810 W. Hiway 54. Wichita, Kansas

Lease Name: DeMoss DB KCC AUB Well No. 2

Location: C N/2 SE NW Sec. 12 Twp. 26 Rge. 2 (E) NW

County Sedgwick Total Depth 2842' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pulley was instructed to plug the well as follows:

- 8 5/8" 2169' -Circulated w/cement. 5 1/2" -2832' -Cemented. Sand hole to 2800'.
- 5 SSax. cement 2800' to 2750'. Mud 2750' to 180'. Bridge 180' to 170'.
- 25 Sax. cement 170' to 100'. Mud 100' to 40'. Bridge 40' to 30'.
- 10 Sax. cement 30' to 0. Pulled 2400' -5 1/2" -pipe.

Very truly yours,

Hugh Scott
Conservation Division Agent