

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

245 North Water
Wichita, KS 67202

API Number 15-173 - 20,331-00-00

Operator's Full Name Brandt Oil Company

Complete Address 1200 Douglas Bldg., Wichita, Ks. 67202

Lease Name Kocour Well No. # 11

Location C. N $\frac{1}{2}$ S $\frac{1}{2}$ NW $\frac{1}{4}$ Sec. 16 Twp. 26 Rge. 2 (East) (~~West~~)

County Sedgwick Total Depth 2916'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Brandt Drlg. Co. Inc.

Address Same as above License No. _____

Operation Completed: Hour: 7:00 PM Day: 17 Month: 2 Year: 19 81

The above well was plugged as follows:

8 5/8" sur. csg. 210' circ./cemt..

Petro-Log Inc. lost neutron tool in hole, fell to bottom of hole.

United Cementing & Acid Co. Inc. pumped all cement.

Ran drill pipe to 2910'; spotted 50 sx. cemt./ dye mixed water.

Filled hole/mud 220', hulls, plug, pumped 25 sx. cemt.

Filled hole/mud 40', hulls, plug, pumped 12 sx. cemt.

Pumped 3 sx. cemt. in rathole.

Note: pulled drill pipe, dropped 7 7/8" bit in hole upside down.

RECEIVED
CONSERVATION COMMISSION

FEB 19 1981
2-19-81

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-23-81

Signed: Alow Thompson
Conservation Division Agent

INV. NO. 8599-E