

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT - 5 1979
10-5-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 173 - 20218 - 00 - 00 (of this well)

Operator's Full Name Wiley Ash Jr.
Complete Address 260 N. Rock Road Suite 105 Wichita, Ks 67206
Lease Name Baylardt Twin ANB KCC Well No. # 1 (Twin)
Location 40' W NW NW NW Sec. 17 Twp. 26 Rge. 2 (E)
County Sedgwick Total Depth 3439'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling
Address Box 176 Chase, Ks. 67524 License No. # 683
Operation Completed: Hour 2:00 P.M. Day 3 Month 10 Year 1979

The above well was plugged as follows:

8 5/8" casg. 195' - cent, circ. - 4 1/2" casg. 3429' / 100 s x cent.
Sand hole to 3400' / 4 s x cent.
Shot + pulled 2935' 4 1/2" casg. left 494' of casg in hole
Mud to 230', 15' rock bridge to 215'
3 1/2 yds. redi mix to 4' below surface

I hereby certify that the above well was plugged as herein stated.

Signed: Alon Thompson
Well Plugging Supervisor

INVOICED

DATE 10-5-79
INV. NO. 6683-E