



15-193-20048-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 5 1974

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
Wichita, Kansas

8-5-74

Dear Sir:

Mr. Bill Reiter of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Studer Well No. E-1

Location: CNW-NW Sec. 33 Twp. 8 Rge. (E)(W) 36

County: Thomas Total Depth 3464' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Reiter was instructed to plug the well as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.

Circulate hole with heavy mud. Pull DP to 2075' and displace 70 Sx.

cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

Very truly yours,

Geo F. Massey  
Conservation Division Agent