



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-181-2000-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 9 1971  
CONSERVATION DIVISION  
Wichita, Kansas

09-09-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center, Wichita, Kansas.

Lease Name: Hevener Well No. 1

Location: CNW-SE Sec. 12 Twp. 8 Rge. (E)(W) 40

County: Sherman Total Depth 5240' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

386'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 2025'.

Circulate hole with heavy mud. Pull DP to 2250' and displace 100 Sx.  
cement thru DP. Pull DP to 400' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

  
Conservation Division Agent