



15-141-20111-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

September 14, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Harold Malcy of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Midco Exploration, Inc.

Complete Address: 411 Farmers & Bankers Bldg, Wichita, Kansas 67202

Lease Name: Beisner Well No. 1

Location: SW SW NE Sec. 3 Twp. 9 Rge. 15 (W)

County: Osborne Total Depth: 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Malcy was instructed to plug the well as follows:

8 5/8" - 246' - 190 sacks Common 270 gel 3% cc. Ann. 1189'-1224' Elev. 1955.66.
Circulate hole and fill with mud. Pump 60 sacks cement through
drill pipe at 600'. Pump 40 sacks cement through drill pipe
at 240'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls
to 40' and cap hole with 10 sacks cement. Cement rat hole with
5 sacks cement.

Orders by Gilbert Balthazor

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

SEP 16 1981

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent

9-16-81