



15-141-20142-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

July 17, 1982

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Vernon Zorn of Shields Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Mal Operations

Complete Address: Box 33, Russell, Kansas 67665

Lease Name: Beisner Well No. 2

Location: SE NW SE Sec. 5 Twp. 9 Rge. 15 (E) (W)

County: Osborne Total Depth: 3650'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Zorn was instructed to plug the well as follows:

Ann. 1262-1299' Elev. 2025 KB Circulate hole and Fill with mud. Pump 50 sacks cement through drill pipe at 930'. Pump 40 sacks cement through drill pipe at 279'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rat hole with 10 sacks cement. Cement mousehole with 10 sacks cement.

Very truly yours,

Arthur D. Roman  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 06 1982  
CONSERVATION DIVISION  
Wichita, Kansas

8-6-82