



15-141-20125-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil ~~gas~~ this date requested permission to plug the following described well:

Operator's Full Name: Rains & Williamson Oil Company

Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Ks. 67202

Lease Name: Tathenhorst Well No. #1

Location: SE NW SE Sec. 8 Twp. 9 Rge. 15 (E) (W)

County: Osborne Total Depth: 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Bob Delaney was instructed to plug the well as follows:

8 5/8"-250' s. p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate with 10 sacks of cement in rat hole.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1981
CONSERVATION DIVISION
Wichita, Kansas

12-21-81