

State of Kansas



15-41-20072-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Lingreen of Revlin Drlg., Inc. has this
date requested permission to plug the following described well:

Mr. Lingreen guarantees payment of the plugging fee.

Operator's full Name: Graham-Michaelis Corp.

Complete Address: P. O. Box 247, Wichita, Kansas 67201

Lease Name: Beisner Well No. 2-10

Location: C SW SE Sec. 10 Twp. 9 Rge. 15 (EX(W) X

County: Osborne Total Depth 3776' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lingreen was instructed to plug the well as follows:

Fill hole with mud and spot 60 sx cement at 660'.

Fill hole with mud and spot 30 sx cement at 270'. 9-11-80

Fill hole with mud to 40' and 1/2 sx hulls, plus 10 sx cement. 5 sx cement in rat hole.

277' of 8 5/8" surface casing cement circ.

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1980
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent