

State of Kansas



15-141-20033-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1977
10-11-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Oil Inc. has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: Suite 950¹²⁵, N. Market, Wichita, Kansas 67202

Lease Name: Norris Well No. 1

Location: SE SE SW Sec. 18 Twp. 9 Rge. 15 (W) X

County: Osborne Total Depth 3510 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Draper was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 600'.

Fill hole with mud and spot 20 sx cement at 210'.

Fill hole with mud to 40' & 1/2 sx hulls, Plug, & 10 sx cem.

2 sx cement in rat hole.

219' of 8 5/8" surface casing cement circ.

Very truly yours,

Deane L Rankin
Conservation Division Agent