



15-141-20058-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP - 4 1979

CONSERVATION DIVISION
Wichita, Kansas

9-4-79

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Kaba of John O. Farmer, Inc. has this date requested permission to plug the following described well:

Mr. Kaba guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: Box 352, Russell, Kansas 67665

Lease Name: Hachmeister "D" Well No. 1

Location: C Ne SW Sec. 19 Twp. 9 Rge. 15 (W) (X)

County: Osborne Total Depth 3704' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kaba was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 550'.

Fill hole with mud and spot 25 sx cement at 200'.

Fill hole with mud to 40' and 1/2 sx hulls, plug, and

10 sx cement & 5 sx cement in rat hole.

201' of 8 5/8" surface casing cement circ.

Very truly yours,

Quay Rankin
Conservation Division Agent