

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN - 7 1982  
6-7-1982  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Kenney Bieker of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Graham-Michaelis Corporation

Complete Address: Box 247, Wichita, Kansas 67201

Lease Name: Krest Well No. #1-22

Location: SW SW SE Sec. 22 Twp. 9 Rge. 15 (E)  (W)

County: Osborne Total Depth: 3670'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A  X

Other well as hereafter indicated: \_\_\_\_\_

Mr. Kenny Bieker was instructed to plug the well as follows:

8 5/8"-259' s.p. cuc. w/160 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks of cement

2nd plug @ 270' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate 10 sacks of cement in rat hole.

Very truly yours,

  
Conservation Division Agent