



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

August 11, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-141-20102-00-00

Dear Sir:

Mr. Walter Odin of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Ivan Holt Well Servicing, Inc.

Complete Address: Box 401, Russell, Kansas 67665

Lease Name: Harold Beck Well No. 1

Location: SE SE SW Sec. 24 Twp. 9 Rge. 15 (W)

County: Osborne Total Depth: 3653'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Odin was instructed to plug the well as follows:

8 5/8" - 219' - 145 sacks Common 2 1/2 gal 3 1/2 cc/c. Elev. 2031 KB Anhydrite 1310' - 43'
Circulate hole and fill with mud. Pump 50 sacks cement through
drill pipe at 990'. Pump 50 sacks cement through drill pipe
at 300'. Fill hole with mud to 40'. Push plug and 1/4 sack
hulls to 40' and cap hole with 10 sacks cement.
Cement rat hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
08-14-1981
AUG 14 1981
CONSERVATION DIVISION
Wichita, Kansas