



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

November 22, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

15-141-20126-00-00

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers

Complete Address: Box 709, Russell, Kansas 67665

Lease Name: Kreft Well No. A-1

Location: C 5/2 5/2 NW Sec. 26 Twp. 9 Rge. 15 (W)

County: Osborne Total Depth: 3530'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Weiler was instructed to plug the well as follows:

8 3/8" - 259' - 16.5 sacks common Anhi 1276-1314 Elev 2018 KB  
Circulate hole and fill with mud. Pump 50 sacks cement  
through drill pipe at 900'. Pump 50 sacks cement through  
drill pipe at 300'. Fill hole with mud to 40'. Push plug  
and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.  
Cement rat hole with 5 sacks cement. Plug mousehole with 5 sacks cement.

Very truly yours,

[Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1981

CONSERVATION DIVISION  
Wichita, Kansas