

15-193-20040-00-00

9

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Thomas County, Sec. 36 Twp. 8S Rge. 33 (E) W (W)

Location as "NE/CNW/SE" or footage from lines NW NW SE

Lease Owner National Oil Company, Inc.

Lease Name Leak Well No. 1

Office Address 200 W. Douglas, Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 1-25-19 72

Application for plugging filed 1-25-19 72

Application for plugging approved 1-25-19 72

Plugging commenced 1-25-19 72

Plugging completed 1-25-19 72

Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4780 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	340'	-0-


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug #1 @ 1745' w/70 sx cement
Plug #2 @ 370' w/20 sx cement
Plug #3 @ 40' w/10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1972
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Red Tiger Drilling Co. Address 1720 Wichita Plaza, Wichita, Ks. 67202

2-22-72



NOTARY PUBLIC, COUNTY OF Sedgewick, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Farris 1720 Wichita Plaza, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of February, 1972

Virginia K. Albert Notary Public

18-193-20040-00-00

RP

DRILLERS LOG

No.1 Leak

CASING RECORD:

COMPANY: National Oil Co., Inc.

DESCRIPTION:

8 5/8" @ 340'
w/225 sx cement

CONTRACTOR: Red Tiger Drilling Co.

NW NW SE
36-85-33W
Thomas County,
Kansas

COMMENCED: January 13, 1972

COMPLETED: January 25, 1972

TOTAL DEPTH: 4780'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	350	
Shale	350	2295	
Shale & Heavy Mud	2295	2325	
Blane Anhydrite	2325	2345	
Shale & Heavy Mud	2345	2485	
Shale & Heavy Mud	2485	2600	
Shale	2600	2742	
Anhydrite	2742	2774	
Shale & Lime	2774	3580	
Lime	3580	4780	

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1972
CONSERVATION DIVISION
Wichita, Kansas


2-22-72

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Jin Farrice
Jin Farrice

Subscribed and sworn to before me this 17th day of February, 1972.



Virginia K. Albert
Notary Public

My Commission Expires:
7-23-74