

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Tengasco, Inc.  
Address: PO Box 458 Hays, KS 67601  
Phone: (785) 625-6374 Operator License #: ~~32778~~ 32278  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 6-16-08 (Date)  
by: Richard Lacey (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 3631' Bottom: 3678' T.D. 3800'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-145-09518-00-00  
Lease Name: Barstow  
Well Number: #1  
Spot Location (QQQQ): C - NW - SW -  
1980 Feet from  North /  South Section Line  
660 Feet from  East /  West Section Line  
Sec. 14 Twp. 22 S. R. 15  East  West  
County: Pawnee  
Date Well Completed: 10-27-1964  
Plugging-Commenced: 6-17-08  
Plugging Completed: 6-18-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil/wtr	0	194'	8-5/8"	10-13-1964	
		0	3968'	5-1/2"	10-22-1964	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 3 holes @ 930'. Ran tbg to 3450'. Spotted 40 sx 60/40 poz w/ 150# hulls on bottom. Pulled tbg to 900'. Pumped 175 sx cmt to surface in 5-1/2". Shut in 5-1/2" & pumped 135 sx.. Pulled tbg. 2nd day topped 5-1/2" w/ 15 sx. Tied onto 8-5/8". Pumped 100 sx. 465 total sx 60/40 poz 4% gel & 150# hulls.

Name of Plugging Contractor: Fischer Well Service License #: 32332

Address: PO Box 773 Hays, KS 67601

Name of Party Responsible for Plugging Fees: Tengasco, Inc.

State of KS County, Ellis, ss.

Gary Wagner - Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Wagner  
(Address) PO Box 458 Hays, KS 67601


RECEIVED  
KANSAS CORPORATION COMMISSION

SUBSCRIBED and SWORN TO before me this 19<sup>th</sup> day of June, 20 08

Linda K Pfannenstiel My Commission Expires: 2/15/2012  
Notary Public

JUN 20 2008

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



*[Handwritten initials]*