

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: T-N-T Engineering Inc.

Address: 3711 Maplewood Ave, Suite 201 - Wichita Falls, TX 76308

Phone: (940) 691-9157 Operator License #: 33699

Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4/20/08 (Date)

by: Bruce Bayse (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

None Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-25165 -00-00

Lease Name: Rexroat

Well Number: 3

Spot Location (QQQQ): _____ - S/2 - S/2 - NW

2310 Feet from North / South Section Line

1287 Feet from East / West Section Line

Sec. 14 Twp. 17 S. R. 13 East West

County: Barton

Date Well Completed: 4/21/08

Plugging Commenced: 11:15 AM 4/21/08

Plugging Completed: 3:00 PM 4/21/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle (3091'-3170')	Water	Surface	760	8 5/8"	760	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 3300' w/25 sks 15 sks in Rat Hole Circulated 1st Plug 30 minutes w/50Vis Mud

2nd Plug @ 810' w/25 sks 10 sks in Mouse Hole Plugs displaced with mud

3rd Plug @ 344' w/50 sks Total 150 sks 60/40 poz 4% gel w/1/4#CF by Quality Oilwell Cementing

4th Plug @ 40' w/10 sks Completed @ 3:00 PM 4/21/08

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 33699 31548

Address: P. O. Box 763 Hays, KS 67601

Name of Party Responsible for Plugging Fees: T-N-T Engineering, Inc.

State of Texas County, Wichita, ss.

Hal Gill (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Hal Gill

(Address) 3711 Maplewood Ave, Suite 201 - Wichita Falls, TX 76308

SUBSCRIBED and SWORN TO before me this 12th day of June, 2008

Notary Public My Commission Expires: May 26, 2010



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCCPKT Per License

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 20 2008

CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]