

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: PETROLEUM PROPERTY SERVICES INC.
Address: 125 N. MARKET, SUITE 1251, WICHITA KS 67202
Phone: (316) 265-3351 Operator License #: 31142
Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: DUANE KRUEGER (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
BURGESS Depth to Top: 3140 Bottom: 3146 T.D. 3192

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-035-21018-00-00
Lease Name: FRY 'A'
Well Number: 7
Spot Location (QQQQ): APX - NE - NE - NE
330 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 16 Twp. 33 S. R. 6 East West
County: COWLEY
Date Well Completed: 8/26/76
Plugging Commenced: 5/13/08
Plugging Completed: 5/13/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
BURGESS	O&W	3140	3146	8-5/8"	160	0
				4-1/2"	3191	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

PULLED RBP AND TUBING. PERFORATED 350-351' W/4 SHOTS. RAN TUBING TO 3100'. DUMP 8 SX SAND. PULLED UP 2 JOINTS AND CEMENTED BOTTOM W/50 SX 60/40 POZ. PULLED TUBING OUT AND CIRCULATE 80 SX 60/40 POZ TO SURFACE. HOLE STAYED FULL.

Name of Plugging Contractor: MID-KAN WELL SERVICE LLC License #: 33695 **RECEIVED**
Address: P O BOX 326, RUSSELL, KS 67665 **KANSAS CORPORATION COMMISSION**
JUN 19 2008

Name of Party Responsible for Plugging Fees: PETROLEUM PROPERTY SERVICES INC. **CONSERVATION DIVISION**
State of KANSAS County, SEDGWICK, ss. **WICHITA, KS**

MICHEAL S MITCHELL (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 125 N. MARKET, SUITE 1251, WICHITA KS 67202

SUBSCRIBED and SWORN TO before me this 18th day of JUNE 20 08

ROSANN M. SCHIPPERS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 9/28/11

Rosann M Schippers My Commission Expires: 9/28/11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]