

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: F. G. Holl Company, LLC  
Address: PO Box 308, Ellinwood, KS 67526  
Phone: ( ) Operator License #: 5056  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 185-23, 070-0000  
Lease Name: Sleeper Trust  
Well Number: 1-10  
Spot Location (QQQQ): \_\_\_\_\_ - N/2 - N/2 - NW  
330 Feet from  North /  South Section Line  
1250 Feet from  East /  West Section Line  
Sec. 10 Twp. 21 S. R. 11  East  West  
County: Stafford  
Date Well Completed: 03/05/1998  
Plugging Commenced: 5-30-08  
Plugging Completed: 6-3-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	266	
				5 1/2	3452	1675

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3070', bailed 5 sacks cement with bailer, ripped casing at 1800', worked pipe, ripped casing at 1975', pipe came free, pulled casing up to 600', pumped pumped 10 gel, 50 sacks, pulled to 290', pumped 50 sacks, pulled to 40', circulated with 25 sacks to surface, tore down rig, emptied pit, cleaned up location.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 17 2008

Name of Party Responsible for Plugging Fees: F.G. Holl Company, L.L.C.  
State of Kansas County, Sedgwick, ss.


CONSERVATION DIVISION  
WICHITA, KS

~~Loveness Mpanje~~ (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

Loveness Mpanje  
Loveness Mpanje

(Address) 9431 E. Central, Suite 100, Wichita, Kansas 67206



My Appointment Expires SUBSCRIBED and SWORN TO before me this 16th day of June 2008, 20

Betty H. Spotswood My Commission Expires: 04/30/2010  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202