

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
.60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Mai Oil Operations, Inc

Address: PO Box 33, Russell, KS 67665

Phone: (785) 483-2169 Operator License #: 5259

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Hubert Deines (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☐ No If not, is well log attached? ☒ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Formation	Depth to Top:	Bottom:	T.D.

API Number: 15 - 167-20802 -00-02

Lease Name: Louie "A"

Well Number: 1

Spot Location (QQQQ): SW - NE - NW -

990 Feet from ☒ North / ☐ South Section Line

1650 Feet from ☐ East / ☒ West Section Line

Sec. 34 Twp. 14 S. R. 14 ☐ East ☒ West

County: Russell

Date Well Completed: _____

Plugging Commenced: 3-24-08

Plugging Completed: 3-25-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	443	
				5 1/2	3249	2070

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 2910', bailed 5 sacks cement, had 19" stretch, ripped casing at 2210', worked pipe, ripped casing at 2050', pipe came free, pulled casing up to 1450', pumped 100 sacks, 300# hulls, pulled to 800', pumped 35 sacks, 100# hulls, pulled to 500', pumped 30 sacks, 100# hulls, pulled to 250', circulated with 50 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Mai Oil Operations, Inc.

State of Kansas County, Russell, ss.

Allen Bangert

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Allen Bangert

(Address) _____

SUBSCRIBED and SWORN TO before me this _____ day of _____, 20

Ashley Leiker My Commission Expires: 2-15-2012
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 16 2008

CONSERVATION DIVISION
WICHITA, KS

NOTARY PUBLIC - State of Kansas
ASHLEY LEIKER
My Appt. Exp. _____