

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Keith F. Walker Oil & Gas Company, L.L.C.
Address: 103 West Boyd Street- Norman, OK 73069
Phone: (405) 701-0676 Operator License #: 33392
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 5/28/2008 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15 - 025-00035-00-01
Lease Name: Pebbles
Well Number: 27#1R 1-27R
Spot Location (QQQQ): CS/2 - NW - NW - SE
3182 Feet from North / South Section Line
2528 Feet from East / West Section Line
Sec. 27 Twp. 34 S. R. 23 East West
County: Clark
Date Well Completed: 10/17/05
Plugging Commenced: 5/23/08
Plugging Completed: 5/28/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				20"	105'	0
				8 5/8"	883'	0
				4 1/2"	5897'	2292

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 BBL mud down 4 1/2" casing. Set CIPB @ 5449'. Pumped 10 sx cmt. Shot 4 1/2" casing @ 2292'. Laid down same. Pumped 50 sx @ 1200'. Pumped 50 sx @ 900'. Pumped 25 sx @ 270'. Pumped 20 sx @ 40' to surface.

Name of Plugging Contractor: Phil Dollar Oilfield Services, Inc. License #: 33311
Address: P.O. Box 744 Perryton, TX 79070

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 16 2008

Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Company, L.L.C.

State of Cleveland County, Oklahoma, ss.

CONSERVATION DIVISION
WICHITA, KS

Sonya King, Engineer Tech of Keith F. Walker Oil & Gas Company, L.L.C. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) 103 West Boyd Street- Norman, OK 73069



SUBSCRIBED and SWORN TO before me this 11 day of June, 20 08

Rebecca A. Casey
Notary Public

My Commission Expires: 11-10-08