

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections.

Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR CENTENNIAL ENERGY COMPANY #6583

API NO. 15-181-20239 00-00

ADDRESS 11271 Richmond Ave., Suite H-101
Houston, Texas 77082

COUNTY Sherman

FIELD Goodland

**CONTACT PERSON Kenneth E. Kulp

PROD. FORMATION Niobrara

PHONE (713) 497-8146

LEASE ARMSTRONG

PURCHASER KN Natural Gas Co.

WELL NO. 2-2

ADDRESS 205 F St.

WELL LOCATION C NW NW

Phillipsburg, KS 67661

660 Ft. from N Line and

660 Ft. from W Line of

DRILLING Excell Drilling Company

the NW 1/4 SEC. 2 TWP. 8-S RGE. 39-W

CONTRACTOR

ADDRESS 4643 Wadsworth "G"

Wheatridge, Colorado 80033

WELL PLAT

PLUGGING -----

CONTRACTOR

ADDRESS -----

*			

KCC ✓
KGS ✓
(Office Use)

TOTAL DEPTH 1114' PBD 1062'

SPUD DATE 1-17-83 DATE COMPLETED 1-19-83

ELEV: GR 3615' DF 3619' KB 3620'

DRILLED WITH ~~MOBILEX~~ (ROTARY) ~~XXXX~~ TOOLS

Amount of surface pipe set and cemented 368' DV Tool Used? YES

AFFIDAVIT

STATE OF TEXAS, COUNTY OF HARRIS SS, I,

KENNETH E. KULP

OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS GEOLOGIST (FOR) ~~XXX~~ CENTENNIAL ENERGY COMPANY

OPERATOR OF THE ARMSTRONG LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 2-2 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 25 DAY OF January, 19 83, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANTS SAITH NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 17th DAY OF Feb.

CAROLYN BELL

Notary in and for State of Texas

NOTARY PUBLIC

MY COMMISSION EXPIRES: My Commission Expires Aug. 20, 1985

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

RECEIVED
FEB 22 1983
CORPORATION COMMISSION
WICHITA, KANSAS

(S) Kenneth E. Kulp
Carolyn Bell
NOTARY PUBLIC

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SURFACE SANDS & GRAVELS	0'	300'	OGALALLA FORMATION	
SHALE	300'	775'	PIERRE	
SHALE	775'	953'	WHITE SPECKS	
CHALK	953'	990'	NIOBRARA	
SHALE	990'	TD		

No Dst's run.

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	10 3/4"	7"	23	368'	50/50 POZ	110	----
	6 3/4"	4 1/2"	9.5	1083'	50/50 POZ	75	-----

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			3 SPF	.51 TAPE	970' - 990'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
FRAC 100,000# SD 40 TON CO ₂ 800 BBL WTR	970' - 990'

Date of first production

7-14-83

Producing method (flowing, pumping, gas lift, etc.)

FLOWING

Gravity

RATE OF PRODUCTION PER 24 HOURS

Oil ----- bbls.

Gas 696 MCF

Water 0 % 0 bbls.

Gas-oil ratio ----- CFPB

Disposition of gas (vented, used on lease or sold)

SOLD TO K-N

Perforations 970' - 990'

