

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20019-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 9 1969  
CONSERVATION DIVISION  
Wichita, Kansas

6-9-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin-Nadel & Gussman,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Guise Well No. 1

Location SW-SW-NW Sec. 18 Twp. 8 Rge. (E) (W) 36

County Thomas Total Depth 4985'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center Building, Wichita, Kans. License No.     

Operation Completed: Hour 3:30 AM Day 6 Month 6 Year 1969

The Above well was plugged as follows:

311'--8 5/8" Surface casing, cement circulated with 300 Sx.  
Top of Dakota section @ 1750'.

Circulated hole with heavy mud. Pulled DP to 1975' and displaced 100 Sx. cement thru  
DP from 1975' to 1650'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from  
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 6/9/69

INV. NO. 9909-41