

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20020-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin-Nadel & Gussman-Raymond,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Fulwider Well No. 1

Location CSW-NW Sec. 32 Twp. 8 Rge. (E) (W) 36

County Thomas Total Depth 4237'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita License No.       

Operation Completed: Hour 8:00 PM Day 27 Month 6 Year 1969

The above well was plugged as follows:

315'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 1750.

Circulate hole with heavy mud. Pull DP to 1975' and displaced 100 Sx. cement thru DP  
from 1975' to 1650'. Pulled DP to 340' and displaced 20 Sx. cement thru DP from 340'  
to 280'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 3 1969

DATE 7/3/69 CONSERVATION DIVISION  
Wichita, Kansas

Signed: M. L. Dickel  
Well Plugging Supervisor

INV. NO. 47-W 7-3-69