

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 15 1972

CONSERVATION DIVISION
Wichita, Kansas

8-15-72

15-193-20043-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Studer Well No. D-1

Location SW-SW Sec. 33 Twp. 8 Rge. (E) (W) 36

County Thomas Total Depth 4221'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 2:45 PM Day 12 Month 8 Year 1972

The above well was plugged as follows:

265'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1725'.

Circulated hole with heavy mud. Pulled DP to 1950' and displaced 110 Cu. Ft. cement
thru DP from 1950' to 1625'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 8/16/72
INV. NO. 6180-W