

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-193-20048-00-00

85-74

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Studer Well No. E-1

Location CNW-NW Sec. 33 Twp. 8 Rge. (E) (W) 36

County Thomas Total Depth 3464'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Above

Address _____ License No. _____

Operation Completed: Hour 8:00 AM Day 29 Month 7 Year 1974

The above well was plugged as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.
Circulated hole with heavy mud. Pulled DP to 2075' and displaced 70 Sx. cement thru
DP. Pulled DP to 245' and displaced 20 Sx. cement thru DP. Pulled DP, set bridge @ 40'
with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/6/74
INV. NO. 9675-W