

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

15-181-00015-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 91-28

LOCATION SE SE NE

SEC. 11 TWP. 8 RGE. 40W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 ^{KCC} ^{RAF} Lease G.W. Ruckmann

Operator Kingwood Oil Co Address Cravens Bldg Oklahoma City,

Field _____ County Sherman

Total Depth 5573 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 307' circulated with 200 sax cement - 5 1/2" at 4688'
with 275' sax cement behind. Baker Plugs at 4170' - perforations
at 4096' - set plugs at 4070', sand and 5 sax cement.
Pulled 3700' 5 1/2", filled with mud to 300', set rock and 20 sax
cement, mud to 30', set rock and 10 sax cement to bottom cellar.

PLUGGING RECEIVED
STATE CORPORATION COMMISSION
FILE SEC 11 T 8 R 28
BOOK PAGE 91 LINE 28 JUN X 2 1953
CONSERVATION DIVISION
Wichita, Kansas

Edmond Peery
District Conservation Agent
Date 5-31-53