

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas
09-09-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-181-20010-00-00

Operator's Full Name Mack Oil Company,

Complete Address 812 Union Center, Wichita, Kansas.

Lease Name Hevener Well No. 1

Location CNW-SE Sec. 12 Twp. 8 Rge. (E) (W) 40

County Sherman Total Depth 5240'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas License No.

Operation Completed: Hour 5:00 PM Day 4 Month 9 Year 1971

The above well was plugged as follows:

386'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 2025'.

Circulated hole with heavy mud. Pulled DP to 2250' and displaced 100 Sx. cement thru DP from 2250' to 1925'. Pulled DP to 400' and displaced 25 Sx. cement thru DP from 400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 9-10-71

INV. NO. 4311-W