

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20, 142-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Mai Operations

Complete Address Box 33, Russell, Kansas 67665

Lease Name Beisner Well No. 2

Location SE NW SE Sec. 5 Twp. 9 Rge. 15 (East)(West)

County Osborne Total Depth 3650'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Shields Drilling Co. and Allied Cementing Co., Inc.

Address Shields Building, Russell, Kansas License No. _____

Operation Completed: Hour: 5:15 AM Day: 18 Month: July Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Elev. 2025 RB Anhydrite 1262'-99'

Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 930'. 40 sacks cement pumped through drill pipe at 279'. Hole filled with mud to 40'. Plug and 1/2 sack bulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement. Mouschole cemented with 10 sacks cement.

Cemented with 50/50 Pozmix w/2% gel and 3% C.C.

Amount of Surface Casing: 8 5/8" - 273' - 150 sacks Common

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Too many hours.

RECEIVED
STATE CORPORATION COMMISSION
AUG 06 1982
CONSERVATION DIVISION
Wichita, Kansas
INVOICE
DATE 8-9-82
INV. NO. 811-W

Signed: [Signature]
Conservation Division Agent

8-6-82