

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,150 00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Shields Oil Producers, Inc. 5184

Complete Address Box 709, Russell, Kansas 67665

Lease Name Luhman Well No. 1

Location NE NE NW Sec. 6 Twp. 9 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3660

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools and Allied Cementing Co, Inc

Address \_\_\_\_\_ License No. 236

Operation Completed: Hour: 11:00 AM Day: 16 Month: September Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows: Elev. 2035 KB Anhydrite 1297-1331'

Circulate hole and fill with mud. Pumped 50 sacks cement through drill pipe at 1100'. Pumped 30 sacks cement through drill pipe at 400'. Hole filled with mud to 40'. Plug and 1/2 sack balls pushed to 40' and hole cemented to base of collar with 10 sacks cement. Rathole cemented with 10 sacks cement. Mouschole cemented with 10 sacks cement.

Cement used: 50/50 Premix w/2% gel and 3% C.C.

Amount of Surface Casing: 8 5/8" - 394-240 Sacks Common Quikset

I hereby certify that the above plugging instructions were given as herein stated.

Signed: \_\_\_\_\_  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Busy in Saline and Rice Counties.

RECEIVED 9-24-82  
STATE CORPORATION COMMISSION

SEP 24 1982

CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Conservation Division Agent

VOICED

DATE 9-27-82

INV. NO. 1265W