

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20,125-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Rains & Williamson Oil Company

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Tothenhorst Well No. #1

Location SE NW SE Sec. 8 Twp. 9 Rge. 15 (East)(West)

County Osborne Total Depth 3710'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Company

Address 435 Page Court, 220 W. Douglas, Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 2:00PM. Day: 13th Month: Dec. Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-250' s. p. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulate with 10 sacks of cement in rat hole.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICES RECEIVED
DATE 1-20-82
INV. NO. 9006
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
1981

12-21-81