

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-141-20099-00-00

API Number 15-141-20,099 JUN 11 1981

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas  
6-11-81

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name GRAHAM-MICHAELIS CORPORATION

Complete Address 211 NORTH BROADWAY - BOX 247 - WICHITA, KS.

Lease Name FINNEY Well No. #1-10

Location NE-NE-SW Sec. 10 Twp. 9<sup>S</sup> Rge. 12<sup>W</sup> (East) (West)

County OSBORNE Total Depth 3700 FT

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HERSCROMBIE DRILLING COMPANY, INC.

Address 801 UNION ST WICHITA, MO. License No. \_\_\_\_\_

Operation Completed: Hour: 10:00 AM Day: 10<sup>th</sup> Month: JUNE Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

8 5/8" 277 FT SR. CUL. w/ 225 ST COMMON - 2% GEL - 3% CA-CL.  
ORDERED - 95 ST 50/50 PREMIX 4% GEL. 3% CA-CL. + 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1 ST PLUG. @ 480 FT w/ 50 ST CNT.  
2 ND PLUG. @ 300 FT w/ 30 ST CNT.  
3 RD PLUG. - SOLID BRIDGE - HALLS - PLUG. @ 40 FT / 10 ST CNT.  
5 ST IN PAYABLE  
CEMENTED BY ALLOWED CNT.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Wesley Schmit  
Conservation Division Agent

DATE 7-27-81

INV. NO. 5950-W