

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 14 1974

CONSERVATION DIVISION  
Wichita, Kansas

1-14-74

15-193-20047-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Schielke Well No. 1

Location CNW-SW Sec. 16 Twp. 8 Rge. (E) (W) 34

County Thomas Total Depth 4817'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.       

Operation Completed: Hour 8:00 PM Day 10 Month 1 Year 1974

The above well was plugged as follows:

350'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1700'.

Circulated hole with heavy mud. Pulled DP to 1925' and displaced 110 Cu. Ft. cement  
thru DP from 1925' to 1600'. Pulled DP to 370' and displaced 30 Cu. Ft. cement thru  
DP from 370' to 295'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 1/14/74

INV. NO. 8402-W