

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

13-181-19004-0000

RECEIVED 11-16-70  
STATE CORPORATION COMMISSION  
NOV 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Bergsma Well No. 1-A

Location App: SW-SW-SW Sec. 11 Twp. 8 Rge. (E) (W) 38

County Sherman Total Depth 691'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated Lost Hole - CORE HOLE

Plugging Contractor Above

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:00 PM Day 11 Month 11 Year 1970

The above well was plugged as follows:

375'--7" OD Surface casing, cement circulated with 175 Sx. (6 1/2" Hole).  
Surface casing set 100' in shale. Hole drilled below surface with air. Stuck DP on  
bottom leaving 6 drill collars and 1 joint of pipe in hole. Top of fish @ 446'.  
Ran DP to 425' and blew hole dry with air. Ran 25 Sx. cement from 425' to 300'.  
Pulled DP, filled hole with mud to 40', set bridge @ 40' with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. J. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11-16-70

INV. NO. 2855-41