

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-181-20006-0000

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1969
CONSERVATION DIVISION
Wichita, Kansas
3-17-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name Armstrong Well No. 1

Location CSE-NW Sec. 6 Twp. 8 Rge. (E) (W) 39

County Sherman Total Depth 5301'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:00PM Day 11 Month 3 Year 1969

The Above well was plugged as follows:

365'--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 2150'.

Circulated hole with heavy mud. Pulled DP to 2275' and displaced 130 Sx. cement thru
DP from 2275' to 1850'. Pulled DP to 380' and displaced 20 Sx. cement thru DP from
380' to 320'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. D. Dickels*
Well Plugging Supervisor

INVOICED

DATE 3/17/69
INV. NO. 9471-W