

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-141-20, 107-00-00 ✓

Operator's Full Name Graham-Michaelis Corporation

Complete Address Box 274, Wichita, Kansas

Lease Name Hachmeister Well No. 1-31
100'S 100' W E N W N E SW

Location 430' ENL 1550' FWL SW Sec. 31 Twp. 9 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3640'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Revelin Drilling, Inc. and Allied Cementing Co., Inc.

Address Box 88, Russell, Kansas License No. _____

Operation Completed: Hour: 5:45 PM Day: 29 Month: July Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8 3/8" - 260' - 175 sacks Quikset Elev. 2015 KB Anh. 1209' 50"

Hole circulated and Filled with mud. 50 sacks 50-50 Permox
with 4% gel and 3% cat. chl. pumped through drill pipe at 800'.
40 sacks cement ~~cement~~ pumped through drill pipe at 310'.
Hole Filled with mud to 40'. Plug and 1/2 sack balls pushed to
40' and hole cemented with 10 sacks Cement. Reticle Cemented
with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 3 1981
08-03-1981
CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated Wichita, Kansas

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 8-25-81
INV. NO. 6242-W