

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141 20,108-00-00 ✓

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name W-W Oil Company

Complete Address Box 23, Natoma, Kansas 67651

Lease Name Ward "E" Well No. 3

Location 1080' FNL 90's 90'E C S/2 NW NW Sec. 35 Twp. 9 Rge. 15 ~~(East)~~ (West)

County Osborne Total Depth 3501'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations and Allied Cementing Co., Inc.

Address Box 506, Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 6:00 PM Day: 5 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows: 8-5/8"-262'-180 sacks Anh. 1118-53 El.1848 KB

Hole circulated and filled with mud. 50 sacks cement pumped through

drill pipe at 870'. 40 sacks cement pumped through drill pipe at 310'.

Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and

hole cemented to base of cellar with 10 sacks cement. Rathole cemented

with 10 sacks cement.

Cement used: 50-50 Pozmix W/4% gel and 3% CC

RECEIVED  
STATE CORPORATION COMMISSION  
09-09-1981  
SEP - 9 1981  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Conservation Division Agent

DATE 11-4-81  
INV NO 8261-W