

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20, 809 -00-00 (of this well)

Operator's Full Name Rains & Williamso Oil, Inc.

Complete Address 435 Page Ct., 220 W. Douglas, Wichita, Kansas

Lease Name Brown Well-No. 1

Location SW SE SE Sec. 6 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3412

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12:15 P. Day 28 Month 8 Year 1978

The above well was plugged as follows:

RTD 3412' 8 5/8 csg set 206' cwc 150 sk. Plg. Mat. 50-50 poz 8% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.

Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1978
8-31-1978
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: Redman
Well Plugging Supervisor

INVOICED

DATE 8-31-78

INV. NO. 7977W