

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER n/a

LEASE NAME Gamble

WELL NUMBER 6

SPOT LOCATION C NW

SEC. 3 TWP. 9 RGE. 16 (E) of (W)

COUNTY Rooks

Date Well Completed 5/8/59

Plugging Commenced 3/28/85

Plugging Completed 3/28/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Co-Co, Inc./Murfin Drilling Co.

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

Co-Co #5049
MDC #6033

PHONE # (316) 267-3241 OPERATORS LICENSE NO. _____

Character of Well input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6; Hays

Is ACO-1 filed? no If not, is well log attached? no

Producing formation LKC Depth to top 3096' bottom 3358' T.D. 3456'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 7" | 1288' | -- |
| | | | | 4 1/2" | 3447' | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran tbg. to 675' & pumped 85 sx. Common cmt. Cement circ. to surface. Pumped equivalent of 1006' 4 1/2" csg. capacity. Connected to 4 1/2" csg. & pumped 50 sx. Common cmt. & it circ. out 4 1/2" x 7" braden head. SI 4 1/2" x 7" braden head & pumped 10 sx. Common cmt. down 4 1/2" csg. & pressured up to 1800#. Connected to 4 1/2" x 7" braden head & pumped 50 sx. Common cmt. & it circ. it up the 4 1/2" csg. Connected back to 4 1/2" csg. & press. to 500#. Pumped total of 145 sx. down 4 1/2" csg. (1716' of 4 1/2" capacity) and 50 sx. down 4 1/2" x 7" annulus (if additional description is necessary, use BACK of this form.) (477' of 4 1/2" x 7"

Name of Plugging Contractor Murfin Drilling Company License No. 6033 annular capacity)
Address 250 N. Water, Suite 300; Wichita, KS 67202

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.

MAY 14 1985
5-14-1985
CONSERVATION DIVISION
Wichita, Kansas

L. O. Butner, Western Division, Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) By: L. O. Butner

(Address) 250 N. Water, Suite 300; Wichita, KS



SUBSCRIBED AND SWORN TO before me this 23 day of April, 1985

Kerran Redington
Notary Public
Kerran Redington

My Commission expires: 2/6/86

DRILLERS LOG

Gamble #6

Elevation: 1982 D.F.
Casing: 7" G 1288 w/ 300 ex.

Loc: C NW/4
Sec: 3-9S-16W
Rooks County, Kansas
Operator: Cooperative Refinery Ass'n.
Contractor: Shields Drlg. Co.

4 1/2" O 3667 w/ 50 ex.
Comm: 2-18-59 Comp? 3-3-59
Total Depth: 3456'

| <u>From</u> | <u>To</u> | <u>Formation</u> |
|-------------|-----------|------------------------|
| 0 | 635 | Shale, shells, sand |
| 635 | 740 | Sand |
| 740 | 800 | Clay and sand |
| 800 | 1160 | Shale and shells |
| 1160 | 1273 | Redbed |
| 1273 | 1320 | Anhydrite |
| 1320 | 1700 | Redbed and shale |
| 1700 | 1725 | Shale and lime streaks |
| 1725 | 2890 | Shale and lime |
| 2890 | 3456 | Lime |
| 3456 | | R.T.D. |

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1959
4-14-1959
CONSERVATION DIVISION
Wichita, Kansas

(STATE OF KANSAS)

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Gamble #6 well, located C NW/4 of Section 3-9S-16W, Rooks County, Ka.

Subscribed and sworn to before me this 4 day of March 1959.

My commission expires: Sept. 24, 1960.