


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County, Sec. 4 Twp. 9 Rge. (E) 16 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 330' S 330' W of E/4 Corner
Lease Owner Cities Service Oil Co.
Lease Name Holy Cross Well No. 3
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 1-7 1950
Application for plugging filed 1-7 1950
Application for plugging approved 1-7 1950
Plugging commenced 1-7 1950
Plugging completed 1-7 1950
Reason for abandonment of well or producing formation Lost hole @ 3258

If a producing well is abandoned, date of last production 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3258 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	275	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with mud from 3258' to 265'. Set plug, dumped 15 sacks cement, mud to 35', dumped 10 sacks cement, mud and dirt to surface.

3-16-1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. R. C. Cooper
Address Box 751, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Mr. James Porter (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) James Porter

Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of March, 1950

W. E. Smith
Notary Public.

My commission expires 3-17-1951



WELL RECORD

(FIRST HOLE)

Company Cities Service Oil Co. Well No. 3 Farm Holy Cross
 Location 330' South and 330' West of E/4 Corner Sec. 4 T. 9 R. 16W
 Elevation 2006 (2004 Gr.) County State Kansas
 Drlg. Comm. December 13, 1949 Contractor Lohmann-Johnson Drilling Co., Inc.
 Drlg. Comp. December 22, 1949 Acid None
 T. D. 3259' Initial Prod. Lost Hole - P. & A. 1-7-50

CASING RECORD:

8-5/8" @ 275' cem. 150 cc cement

Top Landing 3115'
 Penetration 144'
 Total Depth 3259'

FORMATION RECORD:

surface soil, lime & shale 0-50
 shale & shells 276
 shale & sand 910
 sand 950
 shale & red bed 1060
 shale & shells 1260
 lime 1295
 shale & shells 1650
 shale & lime 1987
 broken lime 2125
 lime 2200
 shale & lime 2238
 broken lime 2819
 shale 2850
 lime 3259 T. D.

SLOPE TESTS (ACID BOTTLE):

500' OK
 1000' OK
 1500' OK
 2000' OK
 2500' OK
 2980' OK

7-7/8" rotary hole.

Drill pipe stuck at approximately 3200'; total depth 3259.

Shot off drill pipe at 2500'.
 Set whipstock at 2288; drilled 2288-2442 and went back into old hole. Plugged hole 1-7-50.

Skidded rig 25' south for second hole.

PLUGGING
 FILE SEC 4-T-9-R16
 BOOK PAGE 132 LINE 48

3-16-1950