

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-01455-00-00
API NUMBER 5/13/60

LEASE NAME Sarver

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 12 TWP. 9 RGE. 16 (W)

COUNTY Rooks

Date Well Completed 6/2/60

Plugging Commenced 9/12/91

Plugging Completed 9/12/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Bowman Oil Company

ADDRESS Box 17 Codell, Ks 67630

PHONE# (913) 434-2304 OPERATORS LICENSE NO. 6931

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/91 (date)

By _____ (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? YES

Producing Formation KO Depth to Top 3211 Bottom 3443 T.D. 3620

Show depth and thickness of all water, oil and gas formations.

WELL RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out	Remarks
		0	203	8 5/8	203	-0-	
		0	3620	1 1/2	3620	None	

RECEIVED
12/20/91
COMMISSION
DEC 20 1991

Describe in detail the manner in which the well was plugged, indicating where the mud/fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perforated anhydrite at 1300', base of Dakota at 850'. Then ran tubing to 2000' and cemented with 150 sacks & 300# hulls, pulled to 1200' and cemented with 100 sacks & 200# hulls, pulled to 600' and cemented to surface with 75 sacks. Pulled tubing out and pumped 20 sacks in casing at 400#.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Inc. License No. _____

Address Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D. Bowman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Louis D. Bowman

(Address) Box 17 Codell, Ks 67630

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 91

Vesta J. Russell
Notary Public

My Commission Expires: July 19, 1992



15-163-01455-00-00

COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


K. G. S. LIBRARY

Company- A. AINSWORTH
Farm- Sarver No. 1

SEC. 12 T. 9 R. 16W
SW SW SW

Total Depth. 3620'
Comm. 3-26-60 Comp. 4-4-60
Shot or Treated.
Contractor. Murfin Drilling Company
Issued. 6-25-60

County Rooks
KANSAS



Elevation. 2064 KB

CASINO:
8 5/8" 203' cem. w/155 sx.
4 1/2" 3629'

Production. 17 BOPD & 3 BW

Figures Indicate Bottom of Formations.

12 1/4" Surface hole	200
shale	530
sand-shale	595
shale-shells	815
shale w/stks. sand	1000
shale-red bed	1285
anhydrite	1327
shells-shale	1685
salt-shale	1770
shale-lime shells	1900
lime-shale	3060
lime	3283
lime	3525
lime-shale	3585
conglomerate	3616
lime Arbuckle	3620
Total Depth	

TOPS:

Anhydrite	1285
Heebner	3167
Lansing	3211

TOPS: SCOUT

Base Kansas City	3443
Conglomerate	3556
Arbuckle	3616

DST #1 3247-3283
DST #2 3280-3325
DST #3 3340-3420

12/26/91
RECEIVED
STATE COMMISSION

DEC 26 1991