

15-143-02797-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

Rooks County, Sec. 13 Twp. 9 Rge. 16 (E) (W)

Location as "NE/CNW&SWK" or footage from lines SW SE SW

Lease Owner G. C. Battin, et al

Lease Name Dorr Well No. 5

Office Address Alma, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 10-17 19 53

Application for plugging filed 10-17 19 53

Application for plugging approved 10-17 19 53

Plugging commenced 10-17 19 53

Plugging completed 10-17 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3535' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	122'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 3535' to 150' - plug at 150', 1/2 sacks hulls on plug and 15 sacks cement to 100' - mud 100' to 40' - plug at 40' - 1/2 sack hulls and 10 sacks cement on plug to surface.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
10/21/53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply & Development Company
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Floyd W. Hild (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Floyd W. Hild

Cherryvale, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1953

Leo L. Veeder

Notary Public.

Nov. 1, 1956

24-2675-S 2-52-20M

PLUGGING
FILE SEC 13 T 9 R 16 W
BOOK PAGE 136 LINE 40



15-163-02797-0000

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for G. C. Battin, et al Farm Dorr No. 5 Depth 3535'
 Contractor Veeder Supply & Development Co. Pipe Run 122' 8 5/8" surface casing
 Location SW SE SW Sec. 13 Twp. 9 Range 16
 Commenced 10-5-1953 Completed 10-17-1953 County Rooks State Kansas

Soil and rock	0	95	95
Rock, shale	95	122	27
Shale, shells, sand	122	1035	913
Shale, shells	1035	1300	265
Anhydrite	1300	1325	25
Red bed, shale, shells	1325	1570	245
Shale, broken lime	1570	1875	305
Shale, lime	1875	2433	558
Lime	2433	2486	53
Lime, shale	2486	3305	819
Lime	3305	3375	70
Lime, shale	3375	3535	160
Total Depth	3535		

Plugged to 150' with mud, 15 sacks cement to 100'
 Mud to 40' with 10 sacks cement to surface.

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath,
 says:

I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby
 know and on oath state that the above drilling log covering the Dorr #5 well in
 Section 13-9-16, Rooks County, Kansas, is true and correct. Further affiant saith
 not.

10/21/53

RECEIVED
COMMISSION

THE VEEDER SUPPLY & DEVELOPMENT COMPANY

BY: Floyd W. Hild.
Floyd W. Hild.

Subscribed and sworn to before me this 19th day of October, 1953.

Leo C. Veeder.
Notary Public

My commission expires Nov. 1, 1956

PLUGGING
 FILE SEC 13 T 9 R 16
 BOOK PAGE 136 LINE 40