

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

4 WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-163-30231-00-00

API NUMBER Completion 11-20-66

LEASE NAME Dorr

WELL NUMBER C-1-C^{KCC} CAP

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 13 TWP. 9 RGE. 16 (E) of (W)

COUNTY Rooks

Date Well Completed 11-20-66

Plugging Commenced 9-13-93

Plugging Completed 9-13-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR A.H. Krueger Jr.

ADDRESS 211 Circle Dr., Hays, Ks 67601

PHONE#(913) 625-6936 OPERATORS LICENSE NO. 6597

Character of Well Oil,

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-13-93 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Kansas City Depth to Top 3228 Bottom 3466 T.D. 3466

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	136'	None
				4 1/2"	3466'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Run in hole with tubing to 3300'. Spot 50 sx. cement w/100# hulls. Pull to 2200'. Spot 50 sx. cement w/100# hulls. Pull to 1100'. Spot 60 sx. cement w/100# hulls to circulate cement to surface. Pull tubing and sq. casing with 25 sx. cement. Sq. 8 5/8" with 25 sx. cement to 600'. Filled top of hole with 1 1/2 yd. cement. Well plugged. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Hays, KS


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.H. Krueger Jr.

STATE OF Kansas COUNTY OF Ellis, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) A.H. Krueger Jr.

(Address) 211 Circle Dr, Hays, Kansas, 67601



SUBSCRIBED AND SWORN TO before me this 23 day of September, 19 93

Dorothy A. Klaus
 Notary Public

My Commission Expires: 12-13-93

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 24 1993
 9/24/93

CONSERVATION DIVISION
 Wichita, Kansas CP-4
 Revised 05-88