

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-1163-03757-00-01

LEASE NAME Tatkenhorst A

WELL NUMBER 1

4950 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 14 TWP. 9 RGE. 16 or (W)

COUNTY Rooks

Date Well Completed 3-23-39

Plugging Commenced 11-22-88

Plugging Completed 11-22-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Harold Krueger Co.

ADDRESS Box 247, Natoma, Kansas 67651

PHONE# (913) 885-4701 OPERATORS LICENSE NO. 5769

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-18-88 (date)

by Dennis Hamel, Hays, Kansas (KCC District Agent's Name).

Is ACO-1 filed? No. If not, is well log attached? No log -- sending card copy

Producing Formation NA Depth to Top _____ Bottom _____ T.D. 3446

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12"	54'	None
				7"	3237'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped in 7" csg. 150 sks cement. Disp. w/52 bbls of water. Pressure to 750#.
Perf. csg. at 1350'. Pumped 75 sks cement, disp. w/28 bbls water. Pressure to 400#. Perf.
@775'. Pumped 150 sks cement. Perf. csg. @60'. Circulated cement to surface w/125 sks cement.
Well plugged. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton

License No. 1000

Address Hays, Kansas

STATE OF KANSAS

COUNTY OF OSBORNE

CONSERVATION DIVISION
Wichita, Kansas

Dean E. Wineland

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean E. Wineland

(Address) Natoma, Kansas 67651

SUBSCRIBED AND SWORN TO before me this 9th day of December, 19 88

Lois A. Doty
Notary Public

My Commission Expires: 12-15-88



