


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Rooks County. Sec. 15 Twp. 9 Rge. 16 (W) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. 330'S 330'E of Center
Lease Owner. Cities Service Oil Company
Lease Name. Casey Well No. 1
Office Address. Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 3-31 19.48
Application for plugging filed. 3-31 19.48
Application for plugging approved. 3-31 19.48
Plugging commenced. 3-31 19.48
Plugging completed. 4-1 19.48
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production. 19.
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. M. A. Rives
Producing formation. Arbuckle Depth to top. 3691 Bottom. Total Depth of Well. 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle Lime	Dry			8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Filled with heavy mud from 3730' to 245' Set Plug dumped 15 sacks cement, heavy mud to 20' Set plug, dumped 20 sacks cement, mud and dirt to surface.

MAY 11 1948
5/11/48

(If additional description is necessary, use BACK of this sheet.)
Correspondence regarding this well should be addressed to. Mr. R. C. Cooper
Address. P.O. Box 751
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Mr. James Porter (employee of owner) or (owner) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter
P.O. Box 553, Russell, Kansas
(Address)



SUBSCRIBED AND SWORN TO before me this 17th day of April 1948
My commission expires 3-17-1951
W. G. Smith
Notary Public.

PLUGGING
FILE SEC 15 T 9 R 16
BOOK PAGE 20 LINE 13

S-163-02931-0000

WELL RECORD

Company Cities Service Oil Co. Well No. 1 Farm Cuscoy
 Location 330' South and 330' East of Center Sec. 15 T. 9 R. 16N
 Elevation 2104 (2101 Gr.) County _____ Rocks _____ State Kansas
 Drg. Comm. March 12, 1948 Contractor Corbett-Harbour Drilling Co.
 Drg. Comp. March 30, 1948 Acid _____
 T. D. 3730' Initial Prod. None - Dry Hole (P. & A.)

CASING RECORD:

8-5/8" x 248' con. 150 ex con. and
100% C.C.

FORMATION RECORD:

shale & shells	0-250
shale	570
sand & shale	900
shale	1345
anhydrite	1375
shale & lime	2225
lime	2295
shale & lime	2350
shale	2505
lime & shale	2740
shale & lime	2900
lime & shale	3010
shale & lime	3115
lime	3275
shale & lime	3325
lime	3415
lime & shale	3470
lime	3610
conglomerate	3700
lime	3730 T. D.

Top Topoka	3000'
Top Lansing	3270'
Top Conglomerate	3611'
Top Weathered Simpson Dolomite	3591'
Top Simpson Shale	3708'
Top Arbuckle	3714'
Penetration	16'
Total Depth	3730'

SLOPE TESTS: 1500' OK (Acid Bottle)
 3000' OK (Syfo)

PLUGGING
 FILE SEC 15 T 9 R 16N
 BOOK PAGE 20 LINE 13

MAY 11 1948

5/11/48