

15-163-03603-0000

Form CP-4  
Rev. 12-15-80

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY \_\_\_\_\_ Rooks SEC. 15 TWP. 9 RGE. 16 NE/W  
Location as in quarters or footage from lines:  
NE-NE-NE

	15		

Locate Well  
correctly on above  
Section Platt.

Lease Owner Harold Krueger Co.  
Lease Name Tatkenhorst D Well No. Y 2  
Office Address P.O. Box 247, Natoma, Kansas 67651  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed Old well. No logs.  
Application for plugging filed 3-29-83  
Plugging commenced 5-4-83  
Plugging completed 5-4-83  
Reason for abandonment of well or producing formation No Production

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
Producing formation KC Lime Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3233

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
KC Lime	Oil			5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Mixed 200 sks. 50/50 pozmix with 6% gel, 4%cc. and 4 sks. of hulls.  
Released plug and pumped to 750 ft. It was on vaccum. Let it suck to 900 ft.  
Shut it in. Perforated at 750 ft. Mixed 100 sks. 50/50 pozmix with 6%gel and 4% cc.  
Released plug. Got cement down to 550 ft. Pressure held at 400 PSI. Released it.  
Perforated at 350 ft. Mixed another 200 sks. of cement with additives. Cement  
circulated. Shut in well. Job complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton, Hays, Kansas

STATE OF KANSAS COUNTY OF OSBORNE, ss.  
Dean Wineland (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Dean Wineland  
Natoma, Kansas 67651  
(Address)

SUBSCRIBED AND SWORN TO before me this 12<sup>th</sup> day of May, 19 83

Della M. Richmond  
Notary Public.

My Commission expires: 7-12 1984 RECEIVED STATE CORPORATION COMMISSION

5/13/83 MAY 3 1983  
CONSERVATION DIVISION  
Wichita, Kansas

DELLA M. RICHMOND  
STATE NOTARY PUBLIC  
OSBORNE COUNTY, KANSAS  
My Appt. Exp. \_\_\_\_\_