

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Centennial Energy Company

API NO. 15 - 181 - 20255-00-00

ADDRESS 21515 Hawthorne Blvd. Ste. 625

COUNTY Sherman

Operator # 6583

Torrance, California 90503-6595

FIELD Goodland

**CONTACT PERSON Earle T. Casler, Jr.

PROD. FORMATION Niobrara

PHONE (213)540-9121

LEASE Dallman

PURCHASER K N Energy, Inc.

WELL NO. 1-10

ADDRESS P.O. Box 15265

WELL LOCATION NE 1/4 NE 1/4

Lakewood, Co. 80215

330 Ft. from N Line and

DRILLING Excell Drilling Co.

330 Ft. from E Line of

CONTRACTOR ADDRESS 4643 Wadsworth Blvd. Suite G

the NE 1/4 SEC. 10 TWP. 8-S RGE. 40-W

Wheatridge, Co. 80033

PLUGGING Not Plugged

CONTRACTOR ADDRESS

RECEIVED STATE CORPORATION COMMISSION NOV 5 1983 CONSERVATION DIVISION Wichita, Kansas

WELL PLAT

Well plat grid with 10 in the center and an asterisk in the top right corner.

KCC KGS (Office Use)

TOTAL DEPTH 1298' PBTD 1261'

SPUD DATE 9-13-83 DATE COMPLETED 9-20-83

ELEV: GR 3665' DF 3669' KB 3671'

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 301' DV Tool Used? NO

AFFIDAVIT

STATE OF California, COUNTY OF Los Angeles SS, I,

E. T. Casler, Jr OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Vice President (XXX) (OF) Centennial Energy Company


OPERATOR OF THE Dallman LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1-10 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 21st DAY OF September, 1983, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.



Signature of E. T. Casler, Jr.

SUBSCRIBED AND SWORN BEFORE ME THIS 2nd DAY OF December, 1983

Signature of Jill A. Peterson, Notary Public

MY COMMISSION EXPIRES: June 28, 1986

**The person who can be reached by phone regarding any questions concerning this information. Within 45 days of completion, a witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Sand & Gravels	0'	250'	Ogalalla Formation	
Black Shale	250'	911'	Pierre	
White Specks Shale	911'	1122'	White Specks Sh	
Chalk	1122'	1163'	Niobrara	
Shale	1163'	TD	Shale	
No DSTS or other OH TESTS				

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8.75	7.00	23	301'	Neat	100	3% CaCl 2% Gel
Production	6.25	4.25	9.5	1267'	Neat	75	2% Gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2 spf	3 1/8 ssb	1142' - 1162'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac with 98,000 sand 13000 BBLS H ₂ O	1142' - 1162'

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
SIGW		

RATE OF PRODUCTION PER 24 HOURS	OH	Gas	Water	Gas-oil ratio	CFPS
	0	539.46 bbls. calc. OF MCF	%	--	--

Disposition of gas (vented, used on lease or sold)	Perforations
	1142-1162'