


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rooks County, Sec. 6 Twp. 9S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Jack S. Woodward, Woodward & Co.  
Lease Name Kern Well No. 1  
Office Address 5433 North Dentwood, Dallas, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 6 19 61  
Application for plugging filed May 6 19 61  
Application for plugging approved May 6 19 61  
Plugging commenced May 6 19 61  
Plugging completed May 6 19 61  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3438 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale, Rock & Shells		0	240	8-5/8"	240	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to Bottom feet for each plug set.

Bottom Plug set at 540 feet with 25 sacks cement, 1/2 sack hulls  
Second plug set at 235 feet with 25 sacks cement, 1/2 sack hulls  
Top plug set at 40 feet with 10 sacks cement, 1/2 sack hulls

**RECEIVED**  
STATE CORPORATION COMMISSION  
5-10-1961  
MAY 10 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Bergman Drilling, Inc.  
Address 425 Union Center Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Harold Bergman, Contractor (employer of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman  
425 Union Center Building, Wichita 2, Kansas  
(Address)



Subscribed and sworn to before me this 8th day of May, 19 61  
August 2, 1962  
Norma J. Johnson  
Notary Public.

DRILLERS' LOG

Woodward & Co. #1 Kern  
SE SE SW Section 6-9S-16W  
Rooks County, Kansas

Commenced: April 23, 1961  
Completed: May 6, 1961

Elevation: 1968 KB  
Surface: 8-5/8" at 240 feet with 145 sacks

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 10 1961  
5-10-1961  
CONSERVATION DIVISION  
Wichita, Kansas

0	-	100	Shale and rock	<u>Tops:</u>		
100	-	240	Shale and Shells	Topeka	2852	(- 884)
240	-	550	Shale - Shells - Sand	Heebner	3070	(-1102)
550	-	675	Red Bed	Toronto	3090	(-1122)
675	-	1025	Shale - Shells	Lansing	3111	(-1143)
1025	-	1275	Red Bed	Base Kansas.		
1275	-	1290	Anhydrite	City	3359	(-1391)
1290	-	1310	Anhydrite	Arbuckle	3428	(-1460)
1310	-	1580	Red Bed - Shale - Shells			
1580	-	1780	Shale - Shells			
1780	-	1970	Shale - Shells			
1970	-	2125	Shale - Lime - Shells			
2125	-	2195	Shale and Lime			
2195	-	2280	Lime and Shale			
2280	-	2415	Lime and Shale			
2415	-	2510	Lime and Shale			
2510	-	2585	Shale - Lime			
2585	-	2740	Lime - Shale			
2740	-	2865	Shale - Lime			
2865	-	2920	Lime - Shale			
2920	-	2975	Lime and Shale			
2975	-	3030	Lime			
3030	-	3056	Lime			
3056	-	3074	Lime			
3074	-	3130	Lime			
3130	-	3180	Lime			
3180	-	3220	Lime			
3220	-	3255	Lime			
3255	-	3300	Lime			
3300	-	3331	Lime			
3331	-	3365	Lime			
3365	-	3417	Lime			
3417	-	3425	Lime			
3425	-	3438	Lime			
3438			Total Depth Rotary			

AFFIDAVIT

COUNTY OF SEDGWICK) )  
STATE OF KANSAS - ) SS.

I, do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

*Harold Bergman*  
Harold Bergman

Subscribed and sworn to before me this 9th day of May, 1961.

*Norma J. Johnson*  
Norma J. Johnson, Notary Public



My Commission expires: August 2, 1962