

15-163-02771-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

ROOKS

8 9 16

County. Sec. Twp. Rge. (E) (W) (S) (C)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner BEN F. BRACK OIL CO INC.

Lease Name MCCARTNEY Well No. 1

Office Address 309-10 BROWN BLDG. WICHITA, KANSAS.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 7-3-49 19 49

Application for plugging filed 7-28 19 49

Application for plugging approved 7-28 19 49

Plugging commenced 8-11 19 49

Plugging completed 8-17 19 49

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well E.R. PETTY

Producing formation KANSAS CITY Depth to top 3095 Bottom 3285 Total Depth of Well 3394 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
SURFACE SOIL, SHELS						
SHALE	DRY			85/8	200'	none
KANSAS CITY	dry			5 1/2	3394'	2635' 11"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH CRUSHED ROCK TO 3025'. DUMP FIVE SAX CEMENT ON TOP OF SAME.  
SHOT PIPE OFF AT 2635' PULLED SMAE. FILLED HOLE WITH HEAVE MUD TO 210'. BRIDTED HOLE TO 200' ANDRAN 15 SAX CEMENT ON TOP OF SAME. BRIDGED HOLE ON TOP OF CEMENT AND FILLED WITH HEAVY MUD TO 100' RUN FIVE SOX CEMENT, FILLED HOLE TO THIRTY FIVE FEET. WITH MUD RUN TWELVE SAX CEMENT FILED TO TOP OF HOLE

8-31-49  
RECEIVED  
Conservation Div.

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to BEN F. BRACK OIL CO INC.  
Address 309-10 BROWN BLDG. WICHITA, KANSAS.

AUG 31 1949

STATE CORPORATION COMMISSION

STATE OF KANSAS, COUNTY OF SEDGWICK, SS. LELAND E. BRACK


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leland E. Brack

(Address) 309-10 BROWN BLDG. WICHITA, KANSAS.

SUBSCRIBED AND SWORN to before me this 30 day of August, 19 49.

Commission expires November 5, 1951. Notary Public. Pauline Hendrickson



PLUGGING  
FILE SEC 8 T 9 R 16 W  
BOOK PAGE 110 LINE 11

13-163-02771-00-00

Ben F. Brack Oil Company, Inc.  
310 Brown Building  
Wichita, Kansas

WELL LOG

McCartney #1 - SW SE SE of Section 8, T. 9 S., R. 16 W., Rooks County, Kansas

Commenced: May 30, 1949

Completed: June 13, 1949

Cellar	5'
Surface Soil and Shells	100
Shale and Shells	200
Shale, Red Bed, Shells	845
Shale and Shells	975
Anhydrite	1010
Shale and Red Bed	1200
Shale and Shells	1255
Lime	1300
Shale	1330
Shale and Lime	1620
Lime and Shale	1760
Shale and Lime	1930
Shale	2050
Shale	2100
Lime and Shale	2125
Lime and Shale	2200
Lime and Shale	2315
Lime and Shale	2400
Lime and Shale	2470
Shale and Lime	2550
Lime and Shale	2625
Shale and Lime Streaks	2720
Shale and Lime Streaks	2780
Lime and Shale	2855
Lime and Shale	2920
Lime and Shale	2970
Lime and Shale	2990
Lime	3030
Lime	3075
Lime	3105
Lime	3145
Lime	3185
Lime	3215
Lime	3525
Lime	3265
Lime	3330
Lime	3350
Lime and Shale	3405
Shale and Lime	3445
Conglomerate & Arbuckle	3475
TOTAL DEPTH	3475

Top Arbuckle 3448'

RECEIVED

Conservation Div.

AUG 31 1949

STATE CORPORATION

COMMISSION

KANSAS

8-31-49

The above is a true and correct copy, to the best of my knowledge, of the formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By Ben F. Brack  
President

WITNESS: 8/30/49

DATED: Pauline Hendrickson

PLUGGING  
FILE SEC 8 T 9 R 16  
BOOK PAGE 10 LINE 11